



भारत सरकार  
भारतीय पुरातत्व सर्वेक्षण,  
जयपुर मण्डल,

निविदा सूचना

अधीक्षण पुरातत्वविद्, भारतीय पुरातत्व सर्वेक्षण, जयपुर मण्डल, 70/133-140, पटेल मार्ग, मानसरोवर, जयपुर, राजस्थान, भारत के राष्ट्रपति की ओर से निम्नलिखित कार्य हेतु प्रमाणित एवं उपयुक्त श्रेणी में पंजीकृत एवं पात्र ठेकेदारों/पंजीकृत फर्म से केवल मुहर बंद प्रतिशत दर आधार पर निविदायें आमंत्रित करते हैं।

निम्न वर्णित कार्य की निविदायें दिनांक 02.02.2017 को अपराह्न 3.00 बजे तक प्राप्त की जावेंगी, तथा उसी दिन अपराह्न. 3.30 बजे खोली जावेंगी।

क्र. सं.	कार्य का नाम	अनुमानित लागत ₹	धरोहर राशि ₹
1.	रसायन शाखा कार्यालय भवन जयपुर का मरम्मत एवम विकास कार्य (सम्पूर्ण मद कार्य कराने के लिए)	रु. 3,36,873/-	रु. 6,737/-

जिन ठेकेदारों / पंजीकृत फर्म की मुहर बंद निविदा आवेदन के साथ धरोहर राशि अधीक्षण पुरातत्वविद्, भारतीय पुरातत्व सर्वेक्षण, जयपुर के पक्ष में जारी बैंक मांग-पत्र के रूप में संलग्न नहीं होगी, एवं मुहर बंद निविदा लिफाफे पर कार्य का नाम व निविदा कर्ता का नाम अंकित नहीं होगा वह निविदा अमान्य होगी।

**-: निविदा प्रपत्र के लिए शर्तें :-**

1. ठेकेदार के.लो.नि.वि./ स्थानीय लो.नि.वि./रेल्वे/पी.एण्ड.टी विभाग / एम.ई.एस. / सिंचाई विभाग / भारतीय पुरातत्व सर्वेक्षण विभाग / सरकारी उपक्रम में रजिस्टर्ड होने चाहिए एवं फर्म स्वीकृत होनी चाहिए और वैध TIN एवं PAN होने अनिवार्य हैं ।
2. निविदा प्रपत्र के साथ उपयुक्त श्रेणी में पंजीकरण पत्र एवम TIN एवं PAN की सत्यापित प्रति संलग्न करना होगा अन्यथा निविदा प्रपत्र अमान्य होगा।
3. शर्तें एवं निविदा प्रपत्र उपरोक्त कार्यालय पते पर सभी कार्य दिवसों में पूर्वाह्न 11.00 बजे से अपराह्न: 4.00 बजे तक अपने मूल दस्तावेज जॉच कराने के पश्चात रु0 500/- प्रति का मांगड्राफ्ट अधीक्षण पुरातत्वविद्, भारतीय पुरातत्व सर्वेक्षण के नाम जयपुर (राज.) में देय दिनांक 01.02.2017 तक प्राप्त की जा सकती हैं।
4. निविदा प्रपत्र एवं आवश्यक सूचना भा.पु.स. की वेबसाइट [www.asi.nic.in/](http://www.asi.nic.in/) [www.asijaipurcircle.com](http://www.asijaipurcircle.com) and **Central Public Procurement Portal** पर उपलब्ध है जो कि डाउनलोड कर एवम ₹500/- निविदा प्रपत्र राशि का मांगड्राफ्ट अधीक्षण पुरातत्वविद्, भारतीय पुरातत्व सर्वेक्षण के नाम जयपुर (राज.) में देय निविदा प्रपत्र के साथ संलग्न कर प्रस्तुत कर सकते हैं ।
5. यदि निविदा प्रपत्र बिक्री/प्राप्ति दिवस को अवकाश धोषित होता है, तो ऐसी स्थिति में निविदा प्रपत्र बिक्री/प्राप्ति अगला कार्य दिवस होगा ।

अधीक्षण पुरातत्वविद्

29/1/17

**Archaeological Survey of India, Jaipur Circle, 70/133-140, Patel Marg,  
Mansarover, Jaipur-302020**

<b>Name of office</b>	<b>District/State</b>	<b>Probable time of completion</b>	<b>Last date of sale and submission</b>
Superintending Archaeologist, Archaeological Survey of India, Jaipur Circle, 70/133-140, Patel Marg, Mansarover, Jaipur-302020	Jaipur Rajasthan	2 Months	Date of Sale : 01.02.2017 Date of Opening: 02.02.2017

Estimated Cost : Rs.3,36,873/-  
Price of Tender- : Rs. 500/-

EMD Rs. : Rs. 6,737/-

Contractor's Name.....

Name of Work **Upgradation of Circle office building Science Branch at Jaipur ( Rajasthan )**

**Percentage Rate Tender for execution of complete work**

Item No.	Description and specification of items of work to be executed	Total Estimated quantities to be executed	Time allowed for completion of work	Remarks
1.	Provision of dismantling cement concrete including stacking of waste material and disposal of malba etc. complete.	4.84 cum	60 days from issue of work order.	
2.	Dismantling old damaged cement plaster 20mm thick and racking out of the joints & cleaning the surface for replaster from inner / outer wall & cracked plaster from ceiling etc.	0.88 sqm		
3	Providing & laying the cement concrete in 1:2:4 (1 cement: 2 coarse sand : 4 stone Agg. 20mm down gage) including ramming & watering etc. complete.	4.84 cum		
4	Providing and fixing 25mm thick Kota stone slab flooring over the bed of 20mm thick cement mortar 1:5 ( 1 cement : 5 Coarse sand ) including pointing the joints etc. complete.	48.38 sqm		
5	Provision of 20mm thick cement plaster on stone/ brick wall with cement mortar 1:5 (1 cement: 5 coarse sand) curing etc. complete.	5.46 sqm		
6	Providing & fixing the wooden door 25mm teakwood frame with 10mm water proof plywood including steel fitting etc. complete.	1.80 sqm		
7	Provision for scrapping and cleaning of white wash/distemper/enamel paint from the Walls including washing the surface very carefully with sand paper etc complete.	1586.21 sqm		
8	Provision of oil bound distemper two coat of approved brand and required shade inside the building etc. complete.	979.53 sqm		
9	Provision for apex paint on exterior surface area emulsion (weather proof) on old surface of plaster two or more coat including minor repair of uneven surface by birla/JK wall putty etc the complete,	455.20 sqm		

10	Provision for applying of approved & branded synthetic enamel paint on wooden door & section window by scraping by sand paper for preparing the surface smooth etc. complete.	154.43 sqm		
11	Providing and fixing 25x25x4 mm M.S. iron frame with 1"x1" wire mesh jali including fabrication, labour and material etc. complete (size: 2.30mX1.45m)	3.34 sqm		
			Rs.3,36,873/-	

Signature of the Contractor

Superintending Archaeologist

*[Handwritten signature]*  
24/11/17

